

STANDARD FLOAT POSITIONS ON THE
PRO FLO 500 SLPT2 (500 GPD UNIT) AEROBIC SYSTEM

NOTE TO DESIGNERS AND ENGINEERS:

The 500 SLPT2 System is delivered by Hill Country Concrete Products, Inc. fully assembled with all floats set and all connections made (save source power and distribution lines). We are happy to set the floats on the pump to your specifications at no additional charge to our customer (provided such settings are delivered to us prior to delivery). If no custom settings are given, the following details the standard settings on the 500 GPD unit, which allows for approximately 301 gallons of retention above the alarm float:

STANDARD FLOAT SETTINGS ON 500 SLPT2 SYSTEM (500 GPD All-In-One Unit):

- Alarm On: Approx. 33.5 Inches Above Floor (Approx 301 Gallons Above Alarm)
- Override: Approx. 31 Inches Above Floor
- Pump On: Approx. 12 Inches Above Floor
- Pump Off: Approx. 5 Inches Above Floor

The components of all other (multi-tank) Pro Flo Aerobic Treatment Systems (750 and 1500 GPD Units) will be partially pre-installed by HCCP (diffuser bar, pump, filter, disinfection and quick connect fittings). We will be happy to set the floats per the design if asked prior to delivery at no additional charge, otherwise the installer will set the floats per the design and finish the few final steps of installation.